

Drau bridge Maribor Slovenia

Pre-stressing systems and formwork engineering.
From one source.

Contract

New Construction

General contractor/Client

DARS
Motorway Company

Location

Maribor
Slovenia

Year of execution

2006-2008



Basic data

Length of bridge	765,00 m
Maximum span	125,00 m
Number of sections	12
Pre-stressing system	VBT-BE "Band external"
Maximum tendon length	495,00 m
Quantity of pre-stressing steel	117,00 t

Our Services

- o Technical advice
- o Selection of system
- o Manufacturing
- o Assembling
- o Pre-stressing

