

Inn valley bridge I6

Austria

Pre-stressing systems and formwork engineering.
From one source.

Contract

Post-strengthening

General contractor/Client

ASFINAG Autobahn
Service GmbH

Location

A12 Inntal motorway Innsbruck
Tyrol
Austria

Year of execution

2007-2008



Basic data

Length of bridge	230,00 m
Maximum span	38,00 m
Number of sections	7
Pre-stressing system	VBT-BE "Band external"
Maximum tendon length	190,00 m
Quantity of pre-stressing steel	25,00 t

Our Services

- o Technical advice
- o Selection of system
- o Manufacturing
- o Assembling
- o Pre-stressing

