

Pre-stressing systems and formwork engineering.
From one source.

Contract

New construction

General contractor/Client

Land Nordrhein-Westfalen
Strassen Nordrhein-Westfalen

Location

Wenden
Nordrhein-Westfalen
Germany

Year of execution

2004-2006



Basic data

Length of bridge	126,00 m
Maximum span	35,00 m
Number of sections	4
Pre-stressing system	VBT-BE "Band external"
Maximum tendon length	80,00 m
Quantity of pre-stressing steel	40,00 t

Our Services

- o Technical advice
- o Selection of system
- o Manufacturing
- o Assembling
- o Pre-stressing

