

# Mur bridge - foreshore bridge

## Austria

Pre-stressing systems and formwork engineering.  
From one source.

### Contract

New construction

### General contractor/Client

ASFINAG  
ARGE Strabag/Habau

### Location

Frohnleiten  
S35 Brucker expressway  
Austria

### Year of execution

2014-2015



### Basic data

Length of bridge	160,00 m and 244,00 m
Maximum span	40,00 m and 35,00 m
Number of sections	4 + 7
Pre-stressing system	VBT-KI "Cable internal"
System	KI-12
Maximum tendon length	43,00 m
Quantity of pre-stressing steel	95,00 t

### Our Services

- o Technical advice
- o Selection of system
- o Manufacturing
- o Assembling
- o Pre-stressing
- o Grouting

