

# Limerick tunnel Ireland

Pre-stressing systems and formwork engineering.  
From one source.

## Contract

New construction  
Inner city by-pass

## General contractor/Client

NRA National Roads Authority

## Location

Limerick  
Ireland

## Year of execution

2007-2008



## Basic data

Length of tunnel	500,00 m
Number of segments	5
Segment length	100,00 m
Pre-stressing system	VBT-KI "Cable internal"
Maximum tendon length	100,00 m
Quantity of pre-stressing steel	150,00 t

## Our Services

- o Technical advice
- o Selection of system
- o Manufacturing
- o Assembling
- o Pre-stressing
- o Grouting

