

# Viaduct Rondo Slovenia

Pre-stressing systems and formwork engineering.  
From one source.

## Contract

New construction

## General contractor/Client

DARS  
Motorway Company  
Slovenia

## Location

Pesnica  
Maribor  
Slovenia

## Year of execution

2006-2007



## Basic data

Length of bridge	450,00 m
Maximum span	32,00 m
Number of sections	14
Pre-stressing system	VBT-KI "Cable internal"
Maximum tendon length	100,00 m
Quantity of pre-stressing steel	190,00 t

## Our Services

- o Technical advice
- o Selection of system
- o Manufacturing
- o Assembling
- o Pre-stressing

