

Pre-stressing systems and formwork engineering.
From one source.

Contract

Strengthening

General contractor/Client

ASFINAG
Chembau GmbH

Location

A13 Brenner motorway A13
Gries am Brenner
Austria

Year of execution

2015



Technical data

Length of bridge	1.110,00 m and 250,00 m
Maximum span	72,50 m resp. 35,80 m
Number of sections	31 + 7
Pre-stressing system	VBT-BE "Band external"
System	BE-12
Maximum tendon length	364,00 m
Quantity of pre-stressing steel	85,00 t

Our services

- o Technical advice
- o Selection of system
- o Manufacturing
- o Assembling
- o Pre-stressing

