



Contract

New construction
Pilot scheme
Hybrid construction

General contractor/Client

Strassen Nordrhein-Westfalen
Amt Meschede

Location

Arnsberg-Hüsten
Hochsauerland
Germany

Year of execution

2005-2006

Basic data

Length of bridge	255,00 m
Maximum span	47,00 m
Number of sections	6
Pre-stressing system	VB-T-BIA "Band internal exchangeable" VB-T-BE "Band external"
Maximum tendon length	191,00 m
Quantity of pre-stressing steel	55,00 t

Our Services

- o Technical advice
- o Selection of system
- o Manufacturing
- o Assembling
- o Pre-stressing

