

Pre-stressing systems and formwork engineering.
From one source.

Contract

New construction

General contractor/Client

Autobahndirektion
Nordbayern

Location

Rödental
Bavaria
Germany

Year of execution

2004-2007



Basic data

Length of bridge	852,00 m
Maximum span	58,00 m
Number of sections	15
Pre-stressing system	VBT-KI "Cable internal" VBT-BE "Band external"
Maximum tendon length	198,00 m
Quantity of pre-stressing steel	690,00 t

Our Services

- o Technical advice
- o Selection of system
- o Manufacturing
- o Assembling
- o Pre-stressing

