

Viaduct Zahme Gera

Germany

Pre-stressing systems and formwork engineering.
From one source.

Contract

New construction

General contractor/Client

Freistaat Thüringen

Location

Geraberg
Thüringer Wald
Germany

Year of execution

2000-2003



Basic data

Length of bridge	520,00 m
Maximum span	145,00 m
Number of sections	4
Pre-stressing system	VBT-BE "Band external" VBT-KI "Cable internal"
Maximum tendon length	165,00 m
Quantity of pre-stressing steel	900,00 t

Our Services

- o Technical advice
- o Selection of system
- o Manufacturing
- o Assembling
- o Pre-stressing

