



Contract

New construction

General contractor/Client

Habau Hoch- u. TiefbaugesmbH
Austria

Location

A94 - K26 1a Bridge Wilddurchlass
Germany

Year of execution

2018

Basic data

Length of bridge	42,00 m
Maximum span	approx. 38,00 m
Number of sections	1
Pre-stressing system	VBT-KI "cable internal"
System	KI-19
Maximum tendon length	40,10 m
Quantity of pre-stressing steel	42,848 t

Our Services

- o Technical advice
- o Manufacturing
- o Assembling
- o Pre-stressing
- o Grouting

